BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/07/2016-17 Dated: 27-02-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 05

Name of Work:- Improvements to main and cross roads of Rajiv Gandhi Nagara in Attur ward no 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K SHANKAR REDDY	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no141,PWD SR 2016-17)	Cum	243.00	70.00	Rupees seventy only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in **hard soil** not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5. **No. 5/ Item No. 2.4/ PWD SR 2016-17**	Cum	11.52	240.00	Rupees two hundred forty only
3	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2016-17)	Cum	76 41	5000.00	Rupees five thousand only
4	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no13,sno4.11)	Cum	11.40	6450.00	Rupees six thousand four hundred fifty only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K SHANKAR REDDY	
				Rate	Rate in Words
5	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2016-17,p.no17,s.no4.46)	Tonne,s	0.82	59000.00	Rupees fifty nine thousand only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2 (pwd sr2016-17 p.no15/4.31)	Sqm	40.80	300.00	Rupees three hundred only
7	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no216,sno28.7.9)	Cum	49.50	7000.00	Rupees seven thousand only
8	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.(P.No 174, I.No 22.7)	Sqm	495.00	85.00	Rupees eighty five only
9	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100 mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications(P.No 175, I.No 22.8.1)	Rmtr	38.50	100.00	Rupees one hundred only
10	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2016-17)	Cum	243.00	80.00	Rupees eighty only

K. Sankar Reddy

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.